


Release Description: LV1 1 SLAB-BUL (P#1) PART 1																
Bar Mark	Qty	Size	Total Length	Type	A'	B'	C'	D'	E'	F'	G'	H'	I'	J'	K'	L'
EB5010	123	#5	3'-10"	T9	6 X	2'-10"										
EB5016	68	#5	4'-11"	T9	6 X	3'-11"										
EB5019	37	#5	13'-4"	20	1'-6"	1'-11"	9'-11"									
EB5026	7	#5	9'-4 X	T1	6 X	2'-2"	2'-0"	2'-2"	2'-0"							
EB5036	37	#5	3'-7"	8	10"	1'-11"										
EB5039	5	#5	15'-10 X	T1	6 X	6'-5"	1'-0"	6'-5"	1'-0"							
EB5040	9	#5	18'-6 X	T1	6 X	6'-5"	2'-4"	6'-5"	2'-4"							
EB5042	20	#5	6'-2"	T7		1'-0"	4'-2"	1'-0"								
EB6013	45	#6	27'-6"	T1	8"	8'-9"	4'-4"	8'-9"	4'-4"							
EB6038	45	#6	14'-8"	T1	8"	4'-10"	1'-10"	4'-10"	1'-10"							
EB8012	23	#8	9'-8"	T7		3'-0"	6'-8"									
EB8014	42	#8	15'-9"	20		2'-1"	3'-9"	9'-11"								
EB8024	8	#8	27'-8"	20		2'-6"	3'-3"	22'-0"								
EB8025	2	#8	13'-1"	20		2'-6"	3'-3"	7'-4"								
EB8035	21	#8	5'-11"	8		1'-4"	3'-3"									
EB8037	42	#8	6'-5"	8		1'-4"	3'-9"									
EB10015	16	#10	12'-0"	T7		2'-1"	9'-11"									
EB10041	12	#10	11'-3"	T7		3'-0"	8'-3"									

Release Description: LV1 1 SLAB-BUL (P#1) PART 2																
Bar Mark	Qty	Size	Total Length	Type	A'	B'	C'	D'	E'	F'	G'	H'	I'	J'	K'	L'
EB5008	77	#5	4'-4"	T9	6 X	3'-4"										
EB5023	6	#5	5'-7"	T9	6 X	4'-7"										
EB6017	25	#8	34'-11"	2	1'-4"	33'-7"										
EB8018	25	#8	28'-11"	2	1'-4"	27'-7"										
EB8044	21	#8	18'-5"	T7		2'-6"	16'-0"									
EB8045	20	#8	14'-9"	T7		2'-6"	12'-3"									
EB8046	13	#8	19'-2"	T7		1'-8"	17'-6"									
EB8047	13	#8	15'-5"	T7		1'-8"	13'-9"									



NOTES:

CLEAR COVER FOR SLAB  
BOTTOM = 1"  
TOP = 1"

LAP SCHEDULE

FOR SLAB AT LEVEL 1

f'c = 5000 PSI


REF: S102 (DT. 09/25/2019)

BAR SIZE	TENSION LAP (UNO)	
	TOP	BOT
#3	22"	17"
#4	29"	23"
#5	36"	28"
#6	44"	34"
#7	63"	49"
#8	72"	56"
#9	81"	63"
#10	90"	69"
#11	99"	76"

TOP BARS ARE HORIZONTAL BARS WITH MORE THAN 12" DEPTH OF CONCRETE CAST BELOW THEM.

ALL MATERIAL ON THIS DRAWING SHALL BE ASTM A615 GRADE 60 U.N.O.

PLACING DRAWING APPROVAL AUTHORITY: VERIFICATION OF DIMENSIONS, DETAILS, ETC ARE REQUESTED WHERE INDICATED. IF EACH VERIFICATION IS NOT NOTED OTHERWISE, IT WILL BE ASSUMED TO BE CORRECT AS SHOWN.



LEVEL 1 - AREA KEY PLAN  
REF: S208.1 (DT. 09/25/2019)

LEVEL 1 - BOTTOM UPPER LAYER (POUR #1)

REF: S208.4 & S208.5 (DT. 09/25/2019)